

PURCHASE DESCRIPTION

Materials Upgrade of Powerhouse Roof Guard Rail at Green Peter

Powerhouse, Linn County Oregon

1. SCOPE:

This statement of work will cover the powerhouse roof guard rail specific equipment for the Green Peter Powerhouse, to bring roof access up to DoD and OSHA regulations. , Willamette Valley Project.

2. BACKGROUND:

The Mid-Willamette Valley is comprised of 2 dams Foster and Green Peter, with missions including hydropower generation and flood risk mitigation both of which are critical infrastructure for the region. Of the 2 dams in the Mid-Willamette Valley, Green Peter is remotely operated and unmanned.

The roof at Green Peter Powerhouse is a flat roof with parapet wall surrounding it. The parapet wall is insufficient for fall protection. To bring Green Peters powerhouse roof Fall protection system into compliance and reduce safety vulnerabilities a guardrail system shall be provided.

3. REQUIREMENTS:

Item number	Quantity	Item Part #	Description
1	18	Panel 1 ASSY	2" Schedule 40 Guardrail panel 1 assy.
2	20	Panel 2 ASSY	2" Schedule 40 Guardrail panel 2 assy.
3	2	West Corner Rail ASSY	2" schedule 40 West Corner guardrail
4	2	East Corner Rail ASSY	2" schedule 40 East Corner guardrail
5	84	Mounting Bracket ASSY	Mounting Bracket ASSY

1.1 Build 18 custom 2" schedule 40 pipe guardrail panel 1 assy. per Powerhouse Roof Guardrail Details drawing GPP-9-3-11/2.

1.2 Build 20 custom 2" schedule 40 pipe guardrail panel 2 assy. per Powerhouse Roof Guardrail Details drawing GPP-9-3-11/2.

1.3 Build 2 custom 2" schedule 40 pipe guardrail west corner assy. per Powerhouse Roof Guardrail Details drawing GPP-9-3-11/2.

1.4 Build 2 custom 2" schedule 40 pipe guardrail East corner assy. per Powerhouse Roof Guardrail Details drawing GPP-9-3-11/2.

1.5 Build 84 custom mounting bracket assy. per Powerhouse Roof Guardrail Details drawing GPP-9-3-11/2.

1.6 Hot dip galvanize all guardrail and mounting bracket assemblies after assembly.

Please reference CU-16-0025-3-2_REV-1PowerhouseRoofGuardRailDetails for Exact specifications and outline of galvanization of parts

4. PURCHASE OF:

powerhouse roof guard rail as outlined in requirements section above.

5. PROJECTED COST:

Projected Total Cost: \$32,000

6. SHIPPING:

**Deliver guard rail and mounting brackets to 40386 West Boundary Rd. Lowell Or. 97452
The Government is not responsible for the cost of shipping to Lookout Point Dam.
Supplies shall be delivered between Monday through Thursday 0800 – 1600. Excluding holidays.**